



## ASTM D3034/IB PVC Gravity Sewer Pipe | Gasketed Integral Bell

14' LAY LENGTH PIPE SEGMENTS				
Nom. Pipe Size	Outside Diameter	Joints Per Bundle	Feet Per Bundle	Feet Per Truckload
<b>SDR 35</b>				
4"	4.22	66	924	22,176
6"	6.28	33	462	8,316
8"	8.40	30/36	420/504	5,544
10"	10.50	12	168	3,024
12"	12.50	16	224	2,688
15"	15.30	6	84	1,512
<b>SDR 26</b>				
4"	4.22	66	924	22,176
6"	6.28	33	462	8,316
8"	8.40	30/36	420/504	5,544
10"	10.50	12	168	3,024
12"	12.50	16	224	2,688
15"	15.30	6	84	1,512
<b>SDR 23.5</b>				
4"	4.22	66	924	22,176
6"	6.28	33	462	8,316

20' LAY LENGTH PIPE SEGMENTS				
Nom. Pipe Size	Outside Diameter	Joints Per Bundle	Feet Per Bundle	Feet Per Truckload
<b>SDR 35</b>				
4"	4.22	66	1,320	21,120
6"	6.28	33	660	7,920
8"	8.40	30/36	600/720	5,280
10"	10.50	12	240	2,880
12"	12.50	16	320	2,560
15"	15.30	6	120	1,440
<b>SDR 26</b>				
4"	4.22	66	1,320	21,120
6"	6.28	33	660	7,920
8"	8.40	30/36	600/720	5,280
10"	10.50	12	240	2,880
12"	12.50	16	320	2,560
15"	15.30	6	120	1,440
<b>SDR 23.5</b>				
4"	4.22	66	1,320	21,120
6"	6.28	33	660	7,920

**Note:**

1. These values are for estimating purposes only.